Modular Equipment 20000 Series
Freezer Bases - Stainless Steel Top
Self-contained

L-20162 shown with options

MODEL	LENGTH
L-20138	38"
L-20150	50"
L-20156	56"
L-20162	62"
L-20168	68"
L-20174	74"
L-20180	80"
L-20186	86"

DEPTH
23", 28" OR 32"

SPECIFICATIONS:

TOP: Die-formed construction of one-piece 16 GA stainless steel type 304-#4 finish with 2 5/8" nosing, Backsplash to be 3/8" coved, 6" high x 2 1/8" wide, Sheared ends fitted with recessed 12 GA steel bars for adjoining units, producing a hairline seam

EXTERIOR: Back, bottom, and sides of 20 GA steel with painted enamel finish, Body supported by 14 GA galvanized steel box channels for legs

CONDENSER HOUSING: Fitted with a stainless steel snap-on louvered panel

INTERIOR: Bottom and Back of 22 GA stainless steel type 304-#2B finish, sides of one-piece high impact plastic, Top of aluminum

DOOR JAMS: One-piece high-impact plastic with concealed magnets on perimeter for positive sealing, w/ door jam heaters to prevent gasket freezing

DOORS: Exterior of one-piece die-stamped 22 GA stainless steel type 304-#4 finish, Interior of high-impact plastic, Gasket mounted w/ aluminum strips and screws for easy removability and to ensure a proper seal, Doors mounted on 12 GA spring-loaded self-closing hinges, Stainless handle with stamped grip

SHELVES: One, removable heavy-steel frame epoxy-coated shelf per door

LEGS: 8" high legs standard, 1 5/8" tubing welded to steel plate and fastened to body support channels, Bullet-foot has 1 1/8" of adjustment, All legs are stainless steel

REFRIGERATION: Self-contained unit has a low-temperature balanced system using a hermetically sealed condenser, Forced-air evaporator with protective-coated coil, expansion valve, defrost heater, and timer, System comes assembled with cord and 5-15-P or 5-20-P plug, Base tested to operate between -5 and 0 degrees F

FEATURES

- Available with other modular equipment under one top up to 10 feet in length
- 16 GA reinforced top
- Self-contained unit
- Self-closing doors
- (1) Wire shelf per door
- Refrigeration system has expansion valve & temp. control for rapid recovery
- Uniform integration in design, quality and parts
- Includes defrost heaters, defrost timer

OPTIONS

- Casters (specify working height)
- Compressor Left
- Drawers
- Custom Lengths

# Modular Equipment L-20000 Series - S/S Work Top

DIMENSIONAL DATA

L-20138 | 24" 14"

L-20156 | 18" 24" 14"

L-20168 | 18" 18" 18" 14"

L-20180 | 24" 24" 18" 14"

L-20150 | 18" 18" 14"

L-20162 | 24" 24" 14"

L-20174 | 18" 24" 18" 14"

L-20186 | 24" 24" 24" 14"

| STATISTICAL DATA												
MODEL	LGTH	CAP. CU. FT.			SHELVING (SQ FT)				CONDENSING UNIT ii	VOLTS/ CYCLE/ PHASE	TOTAL AMPS iii	NEMA PLUG	SHIP WT.
		23"	28"	32"	23"	28"	32"	# PER UNT					
L-20138	38"	3.9	4.6	5.6	4.5	5.9	7.0	1	1/4-HP R-404	115v/60/1	7.15	5-15-P	375#
L-20150	50"	5.8	7.8	9.4	7.3	9.5	11.3	2	1/4-HP R-404	115v/60/1	7.15	5-15-P	405#
L-20156	56"	6.9	9.3	11.2	8.6	11.3	13.4	2	1/3-HP R-404	115v/60/1	10.1	5-15-P	445#
L-20162	62"	8.1	10.9	13.1	10.0	13.1	15.5	2	1/3-HP R-404	115v/60/1	10.1	5-15-P	485#
L-20168	68"	9.4	12.5	15.0	11.4	14.8	17.6	3	1/3-HP R-404	115v/60/1	10.45	5-15-P	515#
L-20174	74"	10.6	14.1	16.9	12.7	16.6	19.7	3	1/2-HP R-404	115v/60/1	13.35	5-20-P	545#
L-20180	80"	11.6	15.5	18.6	14.1	18.4	21.8	3	1/2-HP R-404	115v/60/1	13.35	5-20-P	580#
L-20186	86"	12.8	17.1	20.5	15.5	20.2	24.0	3	1/2-HP R-404	115v/60/1	13.35	5-20-P	615#

Standard Self-closing Doors

Optional Refrigerated Drawers

Optional 26" Refrigerated Drawers (adds 2" to unit length)

shown w/ optional full extension drawer slides

Modular Equipment 20000 Series   MECHANICAL DATA

C — Condensing unit wired to junction box 24" AFF, rear of condenser compartment is open for cord to exit 115V/60/1

S — On/off switch 24" AFF with 8 foot cord and plug 5-15-P

D — 5/8" OD copper drain for condensate evaporator 14 1/2" AFF

T — Defrost Timer 24" AFF hard-wired to J-Box

Notes:
i.   Compressor left available
ii. Custom units may require modified BTU ratings and/or condensing unit HP
iii. Optional hot gas condensate evaporator is factory recommended, if electric evaporator is required, add 0.39 AMP to total