

ITEM NO:	
PROJECT:	
DATE:	

Refrigerated Service Drop-In Counter Case - Three Display Levels



	Lengths include end panels
□ DGS2430R	26-1/8"L x 28-5/8"D x 53-3/4"H
□ DGS3630R	38-1/8"L x 28-5/8"D x 53-3/4"H
□ DGS4830R	50-1/8"L x 28-5/8"D x 53-3/4"H

STANDARD FEATURES

- Breeze™ w/ EnergyWise s/c refrigeration (rear access/ventilation)
- Compressor air rear intake, rear discharge
- Counter must be configured to allow air to be drawn in and discharged out the back.
- Glass ends
- Integrated average product temperature of 40°F or less
- NOTE: A vent in the front of the counter is recommended to help dissipate compressor heat.
- NOTE: Height of display case above counter is 29 3/4"
- One year parts & labor; 5 year compressor warranty
- Shelving removable and adjustable on 1" centers
- Tilt-out front glass

Features	Standard	Options
EXTERIOR COLOR	□ Black	□ Stainless steel
INTERIOR COLOR	□ Black	□ Stainless steel
TRIM COLOR	□ Black	□ Silver
UPPER REAR	Clear glass rear sliding doors (26" model swinging)	□ Reflective glass rear sliding doors (n/a on 26" model)
SHELVING	Clear glass shelf, non-lighted	□ Clear glass shelves, lighted (LED)□ Clear glass shelves, lighted (T-8)
ELECTRICAL CONNECT	6' straight blade power cord (self cont.)	□ 6' locking power cord (self cont.) □ Electrical leads (remote)
REFRIGERATION	□ Breeze [™] w/ EnergyWise s/c refrigeration (rear access/ventilation)	 □ Breeze™ w/ EnergyWise s/c refrigeration (front access/ventilation) □ Note: Remote doesn't incl Conds unit. Floor drain reqd. □ Remote w/thermostat, solenoid & TXV
MISCELLANEOUS		□ Rear door lock □ Second year parts & labor warranty (excludes compressor)






Type I - Designed to operate in ambient conditions of 75°F with 55% relative humidity unless noted otherwise in system information below.

Intended Product To Be Displayed Integrated Prod Temp ° F All Unpackaged refrigerated products 40


REAR VIEW

PLAN VIEW

SIDE VIEW







- 1. 16 1/2" TALL, FULL WIDTH OF CASE, OPENING IN BACK OF CABINET OR COUNTER IS REQUIRED TO PULL OUT REFRIGERATION SYSTEM.
 2. REPRESENTS CUTOUT SIZE IN CABINET FOR CASE TO DROP IN TO. SQUARE CORNERS ON CUTOUTS.
 3. BACK OF COUNTER / CABINET MUST BE VENTED PROPERLY FOR ADEQUATE AIRFLOW TO CONDENSOR.
 4. EXIT VENT IN FRONT OF CABINET IS PREFERRED. IF NOT PROVIDED, AIR VENT MUST BE SURE NOT TO MIX WITH INTAKE AIR.
 5. AIR FLOW INTAKE AND EXIT DETAILS ARE REVERSED WITH FRONT PULLOUT REFRIGERATION OPTION.

NOTE: ALL DIMENSIONS APPROXIMATE

© ELECTRICAL JUNCTION BOX (SUPPLIED WITH 6" LEADS OR POWER CORD). ONLY (SUPPLIED WITH 34" OR 112" PVC TUBE).

REFRIGERATION LINE CONNECTION.

SELF-CONTAINED CASE SERVICE ACCESS AREA.

REMOTE FLOOR SINK & UTILITIES ACCESS AREA.

DRY CASE SERVICE ACCESS AREA.

Model Technical Specifications																
Model	L"	L1"	L2"	System Circuit Volts			Phs	Freq	Amps ***	Watts	Wires	NEMA Plug	SST	втин	Ship Wt	Frt Cls
DGS2430R	N/A	26.13	5.00	Self-Contained	Circuit #1	110-120	1	60	6.30	674	2+G	5-15P or L5-15P	N/A	N/A	500	110
DGS3630R	N/A	38.13	5.00	Self-Contained	Circuit #1	110-120	1	60	11.20	1,037	2+G	5-15P or L5-15P	N/A	N/A	550	110
DGS4830R	N/A	50.13	5.00	Self-Contained	Circuit #1	110-120	1	60	11.20	1,043	2+G	5-15P or L5-15P	N/A	N/A	650	110

*** Does not include electric defrost on freezer models.

Regulatory Approvals:





Important Notes:

888 E. Porter Rd.

Ph. 231-798-8888 Fx. 231-798-4960

Muskegon, MI 49441

www.structuralconcepts.com

- 1) ELECTRICAL NOTE: If GFCI is required, a GFCI breaker MUST be used in lieu of a GFCI receptacle
- 2) Back side of counter must be open or vented the full length of the unit to allow proper ventilation for the refrigeration system.
- 3) A vent in the front of the counter recommended to help dissipate compressor heat.
- 4) Height of display case above counter is 29 3/4"